GRS IX–5]

Previous references
me 72 2883 / - 4

(1923 . me)

File No 72 - 23
Serial Nos. 526

Later references

Preserve

GENERAL AND REVENUE SECRETARIAT.

Serial Nos

Part B for June 24

SUBJECT

Estimate for Rs 8, 300/- for laying a 3" main to serve the higher localities of Mattuvaram Extension

To, The Chief Engineer, the Municipal Commissioner & the Comptroller
Nos 21-23/d 16 6-24
Sanctions the estimate

HP
17/24

Immediate

37949

2

From

JOHN SHORE Esq AMICE MRSANI
CHIEF ENGINEER
BANGALORE

No 14358 Dated 7th June 1924.

To

B. Nagappa, Esq., Bar-at-law ,
Secretary to Government,
Local and Legislative Departments

Bangalore

Ml 72-23

Sir,

Adverting to Government Order No.L.7489-90/Ml.72-23-4 dated the 19th March 1924, I have the honor to forward herewith for obtaining early sanction of Government an estimate amounting to Rs.8,300/- for laying a 3" main to serve higher localities of Malleswaram Extension.

L

0 JUN 1924

GENERAL REVENUE SECTION
L6746.
10 JUN 1924
LOCAL SELF GOVT BRANCH

I have the honour to be,
S i r,
Your most obedient servant,

7-6-24

Chief Engineer of Mysore

Send all papers

3

Report to accompany the estimate for laying a 8" main to serve thehigher localities of the Malleswaram Extension Bangalore City.

Reference:- Chief Engineer's No. S/10961 dated 4-4-24 calling for an estimate for the work.

In the Malleswaram extension the supply in the portions bounded by the 3rd and the 10th main roads on two sides and the 9th and 15th cross roads on the other, is scanty during the mornings. Theground in this locality slopes down at a big gradient from the10th main road to the 1st main road and the feeder line to Malleswaram, is a 6" C.I. Pipe line whi is reduced to 4" at the9th cross road. This main runs is laid brought in the 3rd main road and supplies both the higher and the lower areas and as such the supply to the higher portions is effected by thedraw in the lower portions in spite of careful throttling of the lower valves.

2. To keep up a good supply hitherto, water was being pumped direct into themains at a head of 40' to 50' from the Combined Jewell Filters during the mornings but owing to the present shortage of water, direct pumping had to be given up, and the only way of improving the supply in this locality is by laying an independent main to serve the high-er areas alone.

3. It is therefore proposed to lay a new 8" line from the Jewell Filters along the Subedar Chatram Road and link it up with the 8½" line in the 15th cross road sothat by manipulating thelower valves adequate supplies to all the higher localities can be ensured.

4 The improvement suggested above is very necessary as some more big bungalows are springing up along the Subedar Chatram Road and near the Combined Jewell Filters The proposed line would feed all the houses that may spring in course of time.

5. Necessary provisions have been made [illegible]

estimate for the various specials required.

6. The rates for materials are current ones and are sub-
-ject to fluctuations of the market.

Assistant Engineer in charge,
Water Supply Division,

G R S VI G 24]

SUBJECT

Diary No of letter replied to 6746

Section Annual
File No 72-23
Serial No 6

General and Revenue Secretariat

( )

, *the* 192

Proceedings of the Government of
His Highness the Maharaja of Mysore

Date of issue 14.6.24

Signed by

E.O. no C. 7489-90/
Annual 72-23-4 & 1932
requesting the Chief Engineer to arrange for the execution of laying of a 3" main to serve the Asylum locality of the Malleswaram Extension at a cost not exceeding as stated in the estimate for the necessary ~~Annual~~ Annual Grant for the cost of ~~Annual~~ Annual Grant being met out of the savings on the estimate for the laying of mains & sub mains in the Vishweswarapuram Extension & for duplicating the mains from yelahanka

Gate

May this be

i Printed ?

ii treated as a standing order ?

iii published in the Gazette, English Part ?

iv translated ?

v placed at the disposal of the press ?

vi published in the Gazette, Kannada Part ?

copy sent to Architect
Order Thereon Do.

Lake to Banaswadi

2. Letter no 14350 of
2nd inst from
the Chief Engineer in reference
forwarding for sanction
plan estimate for Rs 8,300/-
for laying a 3" main to
serve the higher localities of
the Kalkeravam Extension.

Order no L 21-23 on estimate & plan

Sanctioned, the work
being met out of the amounts specified
~~for the work~~ in the Govt
order of 19 3 24 read above

To the Chief Engineer in reference
returning the plan & the
sanctioned estimate.

Municipal Commissioner,
Bangalore city handed
through the Executive City Engr. Sd.
Communication to Govt

List of enclosures

Copied by

Examined by

WD 1633—GPB—1,000,00—21 12-[illegible]